PART 1 – GENERAL

1.01 DESCRIPTION

.1 This Section specifies requirements for stripping and storing topsoil.

1.02 RELATED SPECIFICATION

- .1 Construction Specification Section 01570 Environmental Protection
- .2 OPSS 201 Construction Specification for Clearing, Close Cut Clearing, Grubbing and Removal of Surface and Piled Boulders
- .3 OPSS 206 Construction Specification for Grading
- .4 OPSS 802 Construction Specification for Topsoil
- .5 OPSS 805 Construction Specification for Temporary Erosion and Sediment Control Measures

1.03 BASIS OF PAYMENT

- .1 Payment for stripping and storing topsoil to be included in the unit price bid in the Form of Tender for construction of pipeline.
- PART 2 PRODUCTS Not applicable

PART 3 – EXECUTION

3.01 STRIPPING TOPSOIL

- .1 Clear and grub area prior to stripping topsoil.
- .2 Remove topsoil from areas indicated on Contract Drawings or as directed by the Contract Administrator.
- .3 Do not mix topsoil with subsoil or other materials.

3.02 STORING TOPSOIL

.1 Stockpile topsoil in areas approved by Contract Administrator.



- .2 Do not place topsoil in or near dripline of tree stands, within three (3) metres of flood plains or in areas containing natural wildlife habitats.
- .3 Construct perimeter drainage ditches to intercept and divert run-off to adjacent settling ponds.
- .4 Provide temporary erosion control measures in accordance with OPSS 805.

END OF SECTION

